

A STUDY OF WARPAGE AND WELD LINE
DEFECTS ON A PLASTIC COMPOSITE'S MANHOLE
COVER

HAZWANI BINTI KAMARULZZAMAN

© This item is protected by original copyright

SCHOOL OF MANUFACTURING ENGINEERING
UNIVERSITI MALAYSIA PERLIS
MALAYSIA
2010

A STUDY OF WARPAGE AND WELD LINE DEFECTS ON A PLASTIC COMPOSITE'S MANHOLE COVER

by

HAZWANI BINTI KAMARULZZAMAN



Report submitted in partial fulfillment
of the requirements for the degree
of Bachelor of Engineering



UniMAP

April 23, 2010

ACKNOWLEDGEMENTS

First of all, I feel so grateful and Alhamdulillah, praise to Allah s.w.t. with His blessing and mercy, then finally I have been managed to prepare and finished my Final Year Project's report. Here, I would like to thank those who get involved both directly or indirectly in assisted and helping me during the period of this Final Year Project is held.

Special recognition is given to my Final Year Project's supervisor, Mr. Mohd Azaman Bin Md. Deros (lecturer School of Manufacturing Engineering), the person who gave me a lot of advices and comments from the beginning till the end of this project besides guiding me while I'm facing problems and to make sure that I am not in the wrong path during finishing this project. Thanks a lot for his enthusiastic supports and guidance.

Before I forgot, thanks a lot to all my friends which gave me some ideas and suggestions in developing or generating ideas on how to make this project. Although there are many challenges that I have to face, but finally this project has been finish successfully with all supports and favours from my lecturer and my friends included myself effort.

Last but not least, for my family, thank you for all your supports either in material form or encouragement in helping me making and completely finishing this project. Here, I wish to express my appreciation to my entire classmate, whose help and to all individuals whom had help me during final year project to finish it completely and successful. Thank you.

APPROVAL AND DECLARATION SHEET

This project report titled A study of warpage and weld line defects on a plastic composite's manhole cover was prepared and submitted by Hazwani Binti Kamarulzzaman, (Matrix No: 061120186) and has been found satisfactory in terms of scope, quality and presentation as partial fulfillment of the requirement for the Bachelor of Engineering (Manufacturing Engineering) in Universiti Malaysia Perlis (UniMAP).

Checked and Approved by

(Mr. Mohd Azaman Bin Md Deros)

Project Supervisor

**School of Manufacturing Engineering
Universiti Malaysia Perlis**

April 2010

**MENGKAJI KEUPAYAAN UNTUK MENGGANTIKAN BESI BERACUAN
DALAM PEMBUATAN PENUTUP LUBANG DENGAN THERMOPLASTIC
OLEFINS (TPO)**

ABSTRAK

Penutup lubang biasanya diperbuat daripada besi beracuan bagi menampung beban yang tinggi. Kajian ini mengkaji tentang bagaimana hendak memilih dan mengenalpasti material plastik komposit yang paling sesuai bagi menggantikan material asal penutup lubang. Material plastik komposit tersebut mestilah tahan lasak dan mempunyai kos yang rendah. Di samping itu, kajian tentang kesan terhadap parameter yang menyebabkan keledingan dan garis kimpal juga perlu dilakukan bagi mencari material plastik yang paling sesuai. Oleh sebab itu, projek ini bertujuan untuk mendapatkan gabungan parameter yang boleh mengoptimumkan penyebab berlakunya keledingan dan garis kimpal pada material plastik komposit. Projek ini bermula dengan pembikinan awalan rekabentuk penutup lubang bersesuaian dengan material barunya iaitu plastik komposit dan mengenalpasti faktor-faktor yang berkemungkinan akan memberi kesan ke atas tindak balas keledingan dan garis kimpal. Kemudian, eksperimen dijalankan dengan menggunakan perisian Moldflow Plastics Insight (MPI). Lapan parameter telah dipilih termasuklah masa pengisian, suhu acuan, suhu melebur, masa menyejuk, masa pek, tekanan pek, masa suntikan material, dan tekanan suntikan material. Projek bermula dengan mengaplikasikan Rekabentuk Eksperimen (DOE) dengan menggunakan Kaedah Taguchi. Keputusan daripada 18 eksperimen percubaan ini dianalisis untuk mendapatkan keadaan optimum dan nilai anggaran keledingan dan garis kimpal. Langkah terakhir ialah ujian kepastian untuk melihat peratusan kesalahan dibandingkan dengan nilai sebenar. Semua keputusan telah dibincangkan di dalam bahagian 4.

A STUDY OF WARPAGE AND WELD LINE DEFECTS ON A PLASTIC COMPOSITE'S MANHOLE COVER

ABSTRACT

Manhole covers are generally made out of cast iron in order to bear the large loads [1]. This study is about choosing and identifying the most suitable plastic composites material which can best replaced cast iron. The plastics composites must be high durability and low cost. Besides that, the effects of parameter which causes warpage and weld line also must be done to identify the most suitable plastic composite material. Therefore, the goal of this project is to achieve the parameter's combinations which are able to minimize causes of warpage and weld line on plastic part. This project is begin with the design concept of the manhole cover which is suitable with the new material of plastic composite material condition and identifying all factors which may effects warpage and weld line defects responses. Then, the experiment is held by using Moldflow Plastics Insight (MPI) software. Eight parameters have been chosen included the filling time, mold surface temperature, melt temperature, cooling time, packing time, packing pressure, injection time, and injection pressure. This project begins with the Design of Experiments (DOE) by applying Taguchi Method with Orthogonal Array $L_{18}^{2^13^7}$. The results from eighteen trial experiments are analyzed to get the optimum condition and estimate values of warpage and weld line values. The last steps in this project is the confirmation test to see the difference or how far the actual value error percentage from the predicted value. All the results have been discussed in Chapter 4.

TABLE OF CONTENTS

	PAGE
ACKNOWLEDGEMENT	i
APPROVAL AND DECLARATION SHEET	ii
ABSTRAK	iii
ABSTRACT	iv
TABLE OF CONTENTS	v - vii
LIST OF TABLES	viii
LIST OF FIGURES	ix
CHAPTER 1 INTRODUCTION	
1.1 Background of Research	1
1.2 Importance of Study	3
1.3 Research Problem Statement	4
1.4 Objective of the Study	4
1.5 Scope of Study	4
1.6 Organization of the Thesis	5

CHAPTER 2 LITERATURE REVIEW

2.1 Cast Iron	7
2.2 Plastic Composites Material	10
2.3 Plastic Injection Molding Process	11
2.4 Polymer fibers	16
2.5 Parameter Involved	17
2.6 Taguchi Method	18
2.6.1 Orthogonal Array	19
2.6.2 Mean Square Deviation (MSD)	21
2.6.3 Analysis of the Signal-to-noise (S/N) ratio	22
2.6.4 Analysis of Variance (ANOVA)	22
2.6.5 Determine average effect of factors at different levels	23
2.6.6 Optimum Condition Estimation	24
2.7 Application example of Design of Experiment	25

CHAPTER 3 METHODOLOGY

3.1 Introduction	30
3.2 Concept of Study	31
3.3 Material Selection	31
3.3.1 Thermoplastic Olefins (TPO)	31
3.3.2 TPO's Properties	33
3.4 Moldflow Plastics Insight (MPI) Software	34

3.4.1 Moldflow Analysis Steps Framework	34
3.4.2 Moldflow Plastics Insight (MPI) Steps	36
3.5 Design of Experiments (Taguchi Method Steps)	41

CHAPTER 4 RESULTS AND DISCUSSION

4.1 Introduction	44
4.2 Experimental Result	45
4.3 Result of Analysis	49
4.4 Analysis of Variance (ANOVA)	52
4.5 Predicted Optimum Condition and Confirmation Test	56
4.6 Strength of Weld Line	58

CHAPTER 5 CONCLUSION

5.1 Summary	59
5.2 Future Work Recommendations	60

REFERENCES



APPENDICES

Appendix A	64
Appendix B	66
Appendix C	71
Appendix D	91
Appendix E	92

LIST OF TABLES

Tables No.		Page
2.1	Cast iron composition ranges and microstructures	8
2.2	Mechanical Properties of Cast Iron	9
2.3	Example of Orthogonal Array for $L_{18} 2^1 3^7$	20
		25
2.4	Converting Results to MSD and S/N Values (Warpage)	27
2.5	Average Factors Effect (Warpage)	
3.1	Recommended Processing of Thermoplastics Olefin (TPO)	34
3.2	Mechanical Properties of Thermoplastic Olefins (TPO)	34
3.3	The parameter for three levels of selected factors	41
3.4	Experiments run for Orthogonal Array $L_{18} 2^1 3^7$ (Warpage)	42
4.1	Experimental result for warpage defects analysis	45
4.2	Experimental result for weld line defects analysis	48
4.3	Main effects of factors for warpage defects (QC=S)	49
4.4	The best combination parameter of warpage defect minimization	50
4.5	Main effects of factors for weld line defects (QC=S)	51

4.6	The value of weld line defect optimization	51
4.7	Analysis of Variance (ANOVA) for warpage	52
4.8	Analysis of Variance (ANOVA) for weld line	53
4.9	Result of optimum combination factors shown in level condition	56

LIST OF FIGURES

Figures No		Page
2.1	Plastic Injection Molding Machine	13
2.2	Schematic illustration of injection molding with (a) plunger and (b) reciprocating rotating screw.	13
2.3	Sequence of operations in the injection molding of a part with a reciprocating screw.	14
2.4	Illustration of mold features for injection molding	15
2.5	Types of molds used in injection molding	16
3.1	The basic steps for optimizing the part from fill to warpage	35
(3.2)	Manhole Cover	36
3.3	Manhole Covers new design by using IronCAD Software	36
3.4	Dimension of Manhole Covers design	37
3.5	Manhole Covers after meshed by using MPI Software	37
3.6	Gate Location validation by Fast Fill Analysis	38
3.7	The gate location on the meshed model of manhole covers	39

3.8	Molding window graph	39
3.9	Runner system for new design manhole covers	40
4.1	Effect of control factors on warpage ($S/N = S$)	53
4.2	Effect of control factors on weld line ($S/N = S$)	54
4.3	Percentage contribution of design factors on warpage defects	54
4.4	Percentage contribution of design factors on weld line defects	55

© This item is protected by original copyright